



**Vivarium Control Intent
Specification Guide**

Revision A 19 January 2023

Table of Contents

Abstract	3
How to Use this Document	3
Limit of Liability	3
Background and Proposal	3
Vivarium and Laboratory Floor Lighting Control Programming	4
Nomenclature	4
Day/Night Cycle	5
Power Requirements	5
BACnet over IP	5
Area Function Narratives	6
Animal Holding Room	6
Procedure Room	7
System Commissioning Documentation	8
Commissioning Nomenclature	8
Commissioning Checklist	9
Processor Network Configuration Verification	10
Room Commissioning Verification	11
Animal Holding Room Testing Plan Room Number:	12
Procedure Room Testing Plan Room Number:	13

Abstract

Environmental systems in vivaria frequently have more complex specifications than those commonly found controlling general building spaces. Validating that those controls can meet evolving research requirements is essential to project success. Providing the right types of features and flexibility while maintaining high reliability requires diligence and attention to detail.

The purpose of this specification guide is to help lighting and electrical engineering professionals successfully implement a Lutron system on a vivaria project.

How to Use this Document

This specification guide aids design choices with pre-structured sequence of operation and system commissioning documentation that can be used in the absence of client-provided documentation.

The default Sequence of Operations (SoO) information can be adjusted to fit project needs but would require approval by a Lutron technical expert. Figures and tables may be useful in capturing complex and conditional functions. If a SoO is provided by others, an in-depth review by a Lutron technical expert is required. These reviews happen throughout the request for quote and submittal phases of projects as part of the Lutron construction management process.

System testing is performed during the commissioning process to ensure device communication, function, and conformance to SoO. System commissioning and testing is documented. If additional details of performance validation is required, a testing procedure and accompanying documentation into which results are recorded shall be provided for review by a Lutron technical expert.

Limit of Liability

Lutron commercial systems are covered by Lutron's Commercial System Warranty, standard terms and conditions contained in that document are applicable for vivaria systems. Deviations from Lutron's prescribed "Design Considerations" may lower system robustness and increase the chance of erroneous operation. See [Lutron's Illumination Control Overview for Vivaria](#) for additional information on "Design Considerations".

Background and Proposal

Due to their sensitive nature, Lutron takes exceptional care with vivarium projects, and a thorough review of the sequence of operations is part of every system's quotation. The following document shall be provided as a default control narrative and SoO when the provided documentation is not complete.

The intent of this lighting specification is to detail function of the Networked Lighting Control System (NLCS) including interaction between the NLCS and the Environmental Monitoring System (EMS) or Building Management System (BMS). If the project is utilizing a CSI Specification Division 25 "Integrated Automation", then it is recommended to cross reference NLCS and EMS/BMS functionality.

Vivarium and Laboratory Floor Lighting Control Programming

Nomenclature

Animal Holding Room (Vivarium Area)

A room with a controlled environment, often mimicking day and night cycle, where live test subjects are held.

Area

A room or space as defined in the NLCS configuration software. An area may have permanent walls with fixed entry/exit points, or modular walls forming partitionable spaces.

Button Press

An interaction by an occupant with a physical control device to trigger an action in an area controlled by the NLCS. It is common that the button press triggers an action in the same area as it is located, but this is not a requirement. Button presses can trigger actions in areas other than the one it is physically located in, or simultaneous actions in multiple areas.

Critical Power

A backup power source activated on loss of utility power. Space typically retains regular lighting control operations.

Network Lighting Control System (NLCS)

A system of interconnected devices designed to provide control of lighting via automated time driven events, sensor driven events, or user triggered events.

Occupancy Mode

An area function in which an action takes place when an area's occupancy state changes to occupied or unoccupied. Often the action will lights turn on, or brighten, when the area becomes occupied; and lights turn off, or reduce in level, when the area becomes unoccupied.

Occupancy State

A binary value applicable to areas. When any sensor in an area detects an occupant (movement and motion) the area occupancy state is set to occupied. All sensors that have detected an occupant will then start a timer and reset that timer each time it sees an occupant. Once that timer reaches the occupancy timeout it will report vacancy. Once all sensors report vacancy the area occupancy state is set to unoccupied.

Procedure Room (Vivarium Area)

A room with a controlled environment where procedures are run on test subjects.

Scene

A predefined light setting for an area. This may have a single zone at a single level, several zones at a single level, or several zones each at individual levels.

Timeout

The length of time between the last occupant vacating the area and the occupancy state changing.

Vacancy Mode

An area function in which an action takes place only when an area's occupancy state changes to unoccupied. Often the action will lights turn off, or reduce in level, when the area becomes unoccupied. In this application, lighting is triggered manually by occupant button presses.

Zone

An individually controllable light or group of lights contained within an area.

Vivarium and Laboratory Floor Lighting Control Programming *(continued)*

Day/Night Cycle

1. The NLCS will maintain a variable for each Area requiring differing day and night operation. These variables are controlled by the NLCS (default) or EMS/BMS (if specified) via BACnet IP.
2. Default daily schedule:
 - a. At 7 AM activate day mode
 - b. At 7 PM activate night modeThis parameter allows the keypad to change functionality between day mode and night mode per the Area Function Narratives.

Power Requirements

Note: Normal, emergency, and critical power generation and distribution equipment is not provided by Lutron. Design, commissioning, testing, warranty, and maintenance of said equipment, or guarantee of its operation is not part of Lutron's scope of work.

1. Luminaires, NLCS equipment, EMS/BMS equipment, and ancillary equipment involved in control and operation of areas listed under the vivarium specification shall be powered from an uninterruptable Critical Power Source, to preclude loss of function due to loss of utility power.
2. During a loss of utility power, vivarium areas shall continue to operate as if under normal power conditions.
3. Luminaires, NLCS equipment, EMS/BMS equipment, and ancillary equipment involved in control and operation of non-sensitive areas listed under the vivarium specification shall conform to local codes for Emergency/Egress lighting requirements.

BACnet over IP

BACnet IP is a building integration protocol used by BMS to monitor and report on the multi-disciplinary functions of the lab such as lighting, temperature, air quality, etc. This third-party monitoring scheme is recommended as it contributes to the integrity of recorded data.

1. By default, a BACnet/IP Integration license will be provided by Lutron to provide the following features:
 - The NLCS will have public Protocol Implementation Conformance statements (PIC) to list all integration points supported via BACnet/IP.
 - The NLCS will provide integration IDs for all devices in the system that are specified to be visible via BACnet.
 - NLCS BACnet objects will be discoverable over IP.
 - The EMS/BMS will, at a minimum, be able to:
 - a. Control and monitor:
 - Variable state (day/night variable)
 - Lighting scene
 - b. Monitor:
 - Occupancy state
2. Please reference Lutron Quantum and Athena BACnet Protocol Implementation Conformance Statements for additional information and functionality.
 - a. Quantum system-level control: <https://www.Lutron.com/TechnicalDocumentLibrary/3691114.pdf>
 - b. Quantum area-level control: <https://www.lutron.com/TechnicalDocumentLibrary/3691115.pdf>
 - c. Athena: <https://assets.lutron.com/a/documents/3691196.pdf>

Area Function Narratives

Animal Holding Room

Animal Holding Room Control Narrative:

- Diurnal cycle: At 7 AM set day/night variable to “day”, and at 7 PM set to “night”.
- Manual control:

Button	Button Engraving	Function	Day/Night Variable State	Scene Recalled	Purpose
1	Toggle	Scene Toggle	Day	Bright White	Human Day Task Light
				Dim White	Animal Day Normal Light
			Night	Red	Human Night Task Light
				Off	Animal Night Normal Light


Note: Advanced programming required to achieve 1-button keypad’s ability to recall different lighting states based on Day/Night State Variables.

- Automatic occupancy control:

System Input (Occupancy State)	Day/ Night Variable State	Scene Recalled (See Scene Table)
Occupied	Day	Unaffected
Unoccupied		Dim White
Occupied	Night	Unaffected
Unoccupied		Off

- Scene Table:

Scenes	Zones	
	White Light Zone B	Red Light Zone B
	Dimmed	Switched
Off	0	Off
Bright White	100	Off
Dim White	50	Off
Red (Animal Dark)	Off	On
All Lights On (Test)	100	On



QSW2-1BI-xx
Typical 1-button keypad

Area Function Narratives *(continued)*

Procedure Room

Procedure Room Control Narrative:

- Manual control:


Button	Button Engraving	Function	Scene Recalled	Purpose
1	High	Scene Select	High	General Lights: High Intensity
2	Medium	Scene Select	Medium	General Lights: Medium Intensity
3	Low	Scene Select	Low	General Lights: Low Intensity
4	Task	Toggle	Task On	Task Lights: On
			Task Off	Task Lights: Off
5	Off	Scene Select	Off	All Lights: Off
Lower		Lower		General Lights: Lower Intensity
Raise		Raise		General Lights: Raise Intensity

- Automatic occupancy control:

System Input (Occupancy State)	Scene Recalled (See Scene Table)
Occupied	Unaffected
Unoccupied	Off

- Scene Table:

Scenes	Operating Area General Lighting	Operating Area Task Light
	Zone A	Zone B
High	100%	Unaffected
Med	60%	Unaffected
Low	45%	Unaffected
Task On	Unaffected	On
Task Off	Unaffected	Off
Off	Off	Off
▼	Lower	Unaffected
▲	Raise	Unaffected



QSW52-5BRLI-xx-xx
Typical 5-button keypad with Raise/Lower

System Commissioning Documentation

Commissioning Nomenclature

Commissioning Milestones

Below are major project milestones that are essential to successful deployment of a Lutron system. Not all milestones are accomplished on-site.

Lutron Prewire Date(s)

An on-site visit designed to familiarize the electrical contractor with wiring and mounting of system devices, discuss the construction schedule, and review Lutron documentation. A Lutron field service engineer reviews the submittal package, particularly the oneline and the device specifications, and with the electrical contractor, answers questions regarding Lutron project submittals.

Lutron Commissioning Start

First day that Lutron service persons are on-site to begin commissioning the Lutron system.

All Lutron Devices Installed

Date when all Lutron devices are installed and energized according to instructions with all wiring terminations completed.

Lutron Server Commissioned

Lutron software installed and tested functional with connection to all processors.

Lutron Processors Network Configuration Complete

All Lutron supplied devices have been configured with IPv4 information provided by a network admin. Devices are on their permanent network and can correctly communicate with the server.

Lutron Commissioning Complete

All Lutron on-site commissioning activities, with the exception of training and acceptance walk-throughs if applicable, have been completed.

Third-Party Acceptance Walkthrough Complete

Many projects hire third-party testing agencies to validate that systems operate as they were designed/intended to. This is the date that Lutron walked the system with the third-party representative to discuss system operation.

Customer Training Complete

This is the date that Lutron provided the end user, research staff, and/or facility team a full training on system operation and maintenance.

System Turned Over

Lutron has completed all startup activities and the system is under control of the site's staff. Lutron is not expected back on-site, unless otherwise scheduled.

BACnet Enabled on Required Processors

All Lutron equipment has had its BACnet settings configured in accordance with design documents.

BACnet Integration IDs Configured and Transmitted

Lutron has provided a list of "Integration IDs", numbers, and corresponding functions, to the appropriate parties.

BACnet Connection and Control Established by Others

The BACnet integrator has connected to and demonstrated an ability to control the Lutron system.

System Commissioning Documentation *(continued)*

Commissioning Checklist

Milestone	Commissioning Technician	Date
Lutron		
Lutron Prewire Date(s)		
Lutron Commissioning Started		
All Lutron Devices Installed		
Lutron Server Commissioned		
Lutron Processors Network Configuration Complete		
Lutron Commissioning Completed		
Lutron On-site Testing Completed		
Third-Party Acceptance Walkthrough Completed		
Customer Training and Demonstration Completed		
System Turned Over		
BACnet Integration (Optional)		
BACnet Enabled on Required Processors		
BACnet Integration IDs Configured and Transmitted		
BACnet Connection and Control Established by Others		

System Commissioning Documentation *(continued)*

Processor Network Configuration Verification

Processor Room Number	IP Address	Subnet Mask	Gateway	Lutron Configuration Completed By (Date)
Example: Room 101	10.121.233.2	255.255.255.252	10.121.233.1	T Claudius (07/26/2021)

Processor Network Configuration Documentation

This is where network configuration information of Lutron processors is recorded. This information is provided by network admins that are controlling the network on which the vivarium system is operating.

System Commissioning Documentation *(continued)*

Room Commissioning Verification

Room Number (Room Type)	Lutron Controlled Lighting Verified By (Date)	Room Functionally Tested By (Date)	Lutron Commissioning Completed (Date)
Example: Room 101 (Animal Holding)	A Tiberius (07/14/2021)	C Gaius (05/05/2021)	C Christofilakes (04/15/2022)

Lutron Controlled Lighting Verification

Lutron services personnel will test all lighting zones connected to Lutron control devices to confirm they function as expected. These tests do not measure dimming performance or any other light quality factors.

Functional Test

A programmer qualified on the Lutron system specified will verify that programming of rooms matches approved submittals.

System Commissioning Documentation *(continued)*

Animal Holding Room Testing Plan | Room Number: _____

Day/Night Variable	Trigger	Expected Output	Results Pass/Fail (Technician/Date)
Night to Day Transition	Trigger from Vue [Web Based UX]	Day/Night Variable: Day Unoccupied Light Level: Dim White [Scene] Applied: At Time of Event	
Day	Toggle On [Keypad]	Bright White [Scene]	
	Toggle Off [Keypad]	Dim White [Scene]	
	Occupied	Unaffected	
	Unoccupied	Dim White [Scene]	
Day to Night Transition	Trigger from Vue [Web Based UX]	Day/Night Variable: Night Unoccupied Light Level: Off [Scene] Applied: At Time of Event	
Night	Toggle On [Keypad]	Red (Animal Dark) [Scene]	
	Toggle Off [Keypad]	Off [Scene]	
	Occupied	Unaffected	
	Unoccupied	Off [Scene]	

System Commissioning Documentation *(continued)*

Procedure Room Testing Plan | Room Number: _____

Trigger	Expected Output	Results Pass/Fail (Technician/Date)
High [Keypad]	High [Scene]	
Med [Keypad]	Med [Scene]	
Low [Keypad]	Low [Scene]	
Task On [Keypad]	Task Light On [Zone]	
Task Off [Keypad]	Task Light Off [Zone]	
Off [Keypad]	Off [Scene]	
Raise [Keypad]	Raise Lights in Room, Except Task	
Lower [Keypad]	Lower Lights in Room, Except Task	
Occupied	Unaffected	
Unoccupied	Off [Scene]	

Customer Assistance

If you have questions concerning the installation or operation of this product, call Lutron Customer Assistance.

Please provide the exact model number when calling.
Model number can be found on the product packaging.
Example: SZ-CI-PRG

U.S.A., Canada, and the Caribbean: 1.844.LUTRON1
Other countries call: +1.610.282.3800
Fax: +1.610.282.1243

Visit us on the web at www.lutron.com/support

The Lutron logo, Lutron, Athena, and Quantum are trademarks or registered trademarks of Lutron Electronics Co., Inc. in the US and/or other countries.

All other product names, logos, and brands are property of their respective owners.



Lutron Electronics Co., Inc.
7200 Suter Road
Coopersburg, PA 18036 USA