





#### **Table of Contents**

ASHRAE 90.1-2013

# Introduction

Solutions Overview2Summary of Code Requirements4Daylight Zone Requirements5Suggested Code Compliant Solutions6How to Use this Guide8Vive Local Solutions   Layout10
Applications
Atrium Retrofit (Switching)
Break Room Retrofit (Switching)
Classroom20Retrofit (Switching)
Conference RoomRetrofit (Switching)
<b>Egress Corridor</b> Retrofit (Switching)
Open OfficeRetrofit (Dimming 0-10V)

#### **Private Office**

4
6
8
0
2

This document summarizes the lighting and receptacle control requirements for commercial buildings. It is for information purposes only. It is not meant to replace your state's or local jurisdiction's official energy code. The recomendations presented in this guide are based on the originally published code prior to addenda. Please refer to your local building energy code or authority having jurisdiction for your precise requirements. Only the authority having jurisdiction can guarantee code compliance.

# Energy-saving lighting control strategies

Strategy		Potential savings
Max: 100% Max: 80%	<b>High-end trim/tuning</b> sets the maximum light level based on customer requirements in each space.*	10-30% Lighting
Auto On Auto Off	Occupancy/vacancy sensing turns lights on when occupants are in a space and off when they vacate the space.*	20-60% Lighting
Full On Dim	<b>Daylight harvesting</b> dims electric lights when daylight is available to light the space.*	25-60% Lighting
Full On Dim	Personal dimming control gives occupants the ability to set the light level.*	10-20% Lighting
Shade Open Shade Closed	Controllable window shading moves shades to reduce glare and solar heat gain.*	10-20% Cooling
7am: Dim 7pm: Off	<b>Scheduling</b> provides scheduled changes in light levels based on the time of day.*	10-20% Lighting
Full On Dim	<b>Demand response</b> automatically reduces lighting loads during peak electricity usage times.*	30-50% During peak period
Appliance On Appliance Off	Plug load control automatically turns off loads after occupants leave a space.*	15-50% of Controlled loads
Heating Cooling	HVAC integration controls heating, ventilation, and air conditioning systems through a contact closure.*	5-15% HVAC

<sup>\*</sup>Go to lutron.com/references for more information

Codes can sometimes be complicated and difficult to navigate. This commercial application guide provides examples of how Lutron products can be used to meet or exceed code requirements. This guide focuses on Vive and Vive compatible solutions, but our other control systems offer similar features.

# Lutron Product Capabilities: Commercial Applications

						To To
			Local Solution		Panel Sol	utions
		Wallbox	Vive	Vive with wireless hub*	Energi Savr Node	Quantum
	Occupancy sensing		•		•	•
Strate	Multi-level lighting control					
Strategies for code/standards compliance	Daylight harvesting					
code/s	Receptacle control					
tandard	Timeclock				**	•
s compl	Demand response			•	• †	
iance	Energy monitoring					
	BACnet integration					

To learn more about these products and their specifications, go to lutron.com/catalogs.

<sup>\*</sup> For the latest information on products compatible with the Vive wireless hub go to lutron.com/vive.

<sup>\*\*</sup> Requires QS timeclock.

<sup>&</sup>lt;sup>†</sup> Automated Demand Response capability requires signal from a third-party device.

# **Summary of Requirements for Interior Lighting and Receptacle Controls**

ASHRAE 90.1-2013

The requirements listed below are summarized for simplicity and may have other exceptions that were omitted.

	Minimum control type	Description	Code provision
ontrol	Switching	Lighting shall be capable of turning ON and OFF. There shall be at least one manual device for control of the lighting within a space. See code for spaces that allow remote location of control.	9.4.1.1 (a)
Local Control	Multi-level or dimming <sup>1</sup>	Lighting shall be capable of providing at least one level between 30% and 70% of full power, in addition to ON and OFF. There shall be at least one manual device for control of the lighting within a space. See code for spaces that allow remote location of control.	9.4.1.1 (a) 9.4.1.1 (d)
	Timeclock <sup>2</sup>	Interior: Scheduled control, based on time-of-day, turns lighting ON or OFF based on typical occupancy. Occupancy sensors also comply as an alternate to using a timeclock.  Exterior & parking garages: Scheduled control, based on time-of-day and sunrise/sunset, turns lighting ON or OFF based on typical occupancy and daylight (requires astronomical timeclock).	9.4.1.1 (i) 9.4.1.2 (a) & (c) 9.4.1.4 (a), (b), & (c)
ontrol³	Occupancy sensor	Automatic control turns lighting ON upon occupancy or OFF after a vacancy of 20 minutes or less.	9.4.1.1 9.4.1.2 (b)
Automatic Control <sup>3</sup>	Full ON	When initiated by a timeclock or occupancy sensor, lighting is automatically turned ON to maximum lighting power.	9.4.1.1 (h)
Auton	Partial ON	When initiated by a timeclock or occupancy sensor, lighting is automatically turned ON to 50% or less of maximum lighting power.	9.4.1.1 (c)
	Full OFF	When initiated by a timeclock or occupancy sensor, lighting is automatically turned OFF.	9.4.1.1 (h)
	Partial OFF	When initiated by a timeclock or occupancy sensor, lighting is automatically reduced by at least 50% of maximum lighting power (30% for enclosed parking garages and exterior). Automatic full OFF also complies.	9.4.1.1 (g) 9.4.1.2 (b) & (c) 9.4.1.4 (c)
Other	Daylight responsive control <sup>1</sup>	Interior: A sensor which adjusts lighting in response to available daylight is required for sidelight and skylight zones. There must be at least two light levels between ON and OFF. See the "Daylight Zone Requirements" diagrams for more information. Exterior and parking garages: A photosensor can be used as an alternate to the dawn/dusk operation of an astronomical timeclock. The perimeter 20 ft. of parking garages with access to daylight must automatically reduce lighting power in response to daylight.	9.4.1.1 (e) 9.4.1.1 (f) 9.4.1.2 (d) 9.4.1.4 (a)
	Receptacle control	At least 50% of the receptacles in the space shall automatically turn OFF based on typical occupancy or after a vacancy of 20 minutes or less. Plug-in devices do not comply.	8.4.2

For areas being used as a path of egress or fixtures being used for emergency, verify compliance with your local authority having jurisdiction. Acceptance (functional) testing is required for all new construction applications to ensure that control hardware and software are calibrated, programmed and functioning properly (Code provision 9.4.3).

- 1 When multi-level lighting control and/or daylight responsive control is required, Lutron recommends using continuous dimming to allow for smooth light level adjustment and maximized energy savings.
- 2 Lutron recommends using occupancy sensors to achieve automatic on/off requirements in place of a timeclock to maximize energy savings and optimize user experience.

#### **Daylight Zone Requirements**

ASHRAE 90.1-2013


#### **Daylight Zone Requirements:**


Fixtures in the primary and secondary daylight zones must be independently controlled by zone. Sidelighted zones must be controlled separately from toplighted zones.

#### **Daylight Exceptions:**


Daylight control is not required when the total lighting power of a daylight zone is less than 150W or when the total glazing area is less than 20 sq. ft.


#### Sidelighting (Window)





# Toplighting (Skylight)





### **Suggested Code Compliant Solutions**

ASHRAE 90.1-2013

ASHRAE 90.1-2013

**Suggested Code Compliant Solutions** 

The compliant solutions listed below are suggested based on total installed cost, simplicity of design, and basic functional needs for the space. These solutions do not represent the only compliant options to meet lighting and receptacle control requirements. Applications in this guide will illustrate these solutions and/or alternative solutions for advanced functionality.

		Atrium	Break Room	Classroom, Lecture Hall, Training Room	Conference, Multi-purpose Room	Egress Corridor <sup>4</sup>	Lobby
ontrol	Switching						
Local Control	Multi-level or dimming	•	•	•	•	•	•
	Timeclock	<b>*</b>					
	Occupancy sensor		Ø		<b>Ö</b>	<b>Ö</b>	
Automatic Control <sup>2</sup>	Full ON					<b>Ö</b>	
Automatic	Partial ON						
	Full OFF				<b>\overline{\over</b>	<b>\$</b>	
	Partial OFF						
Other	Daylight responsive control	•	•	•	•	•	
O	Receptacle control		•	•	•		

- 1 Retrofit requirements indicated are for lighting alterations greater than 10% of the connected load in a space.
- 2 Manual ON is always permitted for interior applications. Provide manual ON control when no automatic ON is indicated.
- 3 When typically occupied, the sensor provides Partial OFF functionality. When typically unoccupied, the sensor provides Full OFF functionality. For entrances and exits, lights are scheduled to Full OFF when typically unoccupied and Partial OFF at night; daylighting and occupancy sensing are not required.
- 4 For areas not designated as a path of egress, the occupancy sensor must turn lights to full OFF.
- 5 Astronomical timeclock shall ensure all lights are off during daylight hours. Lights should be scheduled to partial OFF during night hours (not required in lighting retrofits). See section 9.4.1.4 for scheduling times.

Diagram key:

New construction

**\(\tilde{\tilie}\tilde{\tilde{\tilde{\tilde{\tilde{\tilde{\tilde{\tilde{\tilde** 

= New construction and retrofit<sup>1</sup>

Open Office (>250 sq. ft.)	Private Office (<250 sq. ft)	Restroom	Egress Stairwell <sup>4</sup>	Storage Room	Facade/ Landscape	Parking Garage (Not Roof) <sup>3</sup>	Other Exterior <sup>5</sup>
				•			
•			•				
					<b>\overline{\overline{\phi}}</b>	<b>*</b>	Ø
<b>Ø</b>	<b>Ø</b>	<b>\overline{\over</b>	<b>\overline{\overline{\phi}}</b>	Ø		<b>*</b>	
			<b>\overline{\overline{\phi}}</b>		<b>\overline{\overline{\phi}}</b>	<b>*</b>	<b>Ö</b>
<b>\overline{\over</b>							
<b>\overline{\over</b>							
			<b>*</b>			<b>*</b>	•
•	•	•	•	•		•	
•	•						

This application guide is designed to help specifiers and contractors understand codes and Lutron controls in a simple manner. Each of the pages will lay out different spaces, the corresponding lighting control products for those spaces, and the way the system is set up in the space.

#### **For Specifiers**

Use this application guide for design suggestions, to understand the way the system operates and to specify the relevant products for each space.


#### **For Contractors**

Use this application guide to understand how the system is installed, the way the system must operate, and to order the correct products for each application.

> Understand how the products are laid out in the space

This guide offers up to three solutions per space type.

- The **Retrofit Solutions** are simple and inexpensive solutions, generally suited for a basic retrofit.
- The **Recommended Solutions** have advanced functionality for greater comfort and energy savings.



# **Vive Local Solutions Layout**

ASHRAE 90.1-2013

This is a high-level overview of the local solutions layout. For individual room requirements refer to the detailed room type solutions in this guide. A single PowPak module can control a single or multiple fixtures. The products shown here are representative of local solutions. Multiple product options are available to meet the needs of the space.



Vive wireless hub\*



PowPak module



- Pico wireless remote control
- Daylight sensor


#### **Vive wireless hub features:**

- · Central control, management, and monitoring of Vive devices via web browser
- Supports astronomic and time-of-day events
- Two contact closure inputs for third-party integration, such as Automatic Demand Response
- · Wi-Fi access for easy commissioning
- Control up to 10,000 sq. ft. with a single hub
- Optional BACnet integration
- \* Go to lutron.com/vive for complete compatibility and design details.



# **Atrium | Retrofit**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-16R-DV-B	PowPak switching module	2	\$ 155.00
	PJ2-2B-GWH-L01	Pico wireless 2-button control	2	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	2	\$ 9.50
	HJS-1-FM	Vive wireless hub	Shared	Consult your local rep for hub pricing and service options.

# Visible System Components



Pico wireless control

# Control Functionality

#### When Occupied:

Manual: Occupant uses wall switches to turn on and turn off general lighting.

#### Timeclock:

Timeclock turns perimeter lights on during normally occupied hours.

Timeclock turns lights off during normally unoccupied hours.

**Control Strategies** 



Scheduling


Lighting Energy Savings\*

10%

<sup>\*</sup> Go to lutron.com/references for more information.

### **Atrium | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	4	\$ 180.00
	LRF2-DCRB-WH	Radio Powr Savr wireless daylight sensor	2	\$ 150.00
	PJ2-4B-GWH-L31	Pico wireless 4-button scene control	1	\$ 45.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50
	HJS-1-FM	Vive wireless hub	Shared	Consult your local rep for hub pricing and service options.

# Visible System Components







Radio Powr Savr wireless daylight sensor

# Control Functionality

#### When Occupied:

Automatic: Overhead lights dim/brighten based on daylight availability. There are two perimeter daylight zones.

Manual: Occupant selects scenes to set desired light levels for all lights.

#### Timeclock:

Timeclock turns lights on to 50% light level during normally occupied hours. Maximum light level is set to 80%.

Timeclock turns lights off during normally unoccupied hours.


# Control Strategies




**Daylight Harvesting** 



**High-end Trim/Tuning** 



**Scheduling** 



Scene Control

Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.


**Code Notes:** Requirements specified for 20-40 ft. atriums. Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

# Break Room | Retrofit

ASHRAE 90.1-2013







Symbol	Model Number	Description	Qty	List Price Each
	MS-VPS6M2-DV-WH	Maestro vacancy sensing switch*	1	\$ 57.20

# Visible System Components



Maestro vacancy sensing switch

# Control Functionality

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually.


#### When Occupied:

Manual: Occupant uses wall switch to turn all lights off.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

# **Control Strategies**



Lighting Energy Savings\*




<sup>\*</sup> Go to lutron.com/references for more information.

<sup>\*</sup> Maestro MS-VPS6M2 is not compatible with the Vive wireless hub.

### **Break Room | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	1	\$ 180.00
	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	LRF2-VKLB-P-WH	Radio Powr Savr wireless corner-mount vacancy sensor	1	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# Visible System Components






Pico wireless control

Radio Powr Savr wireless corner-mount vacancy sensor

# **Control Strategies**



Occupancy/Vacancy



**High-end Trim/Tuning** 



Plug Load Control

# **Control Functionality**

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually. Maximum light level is set to 80%.

Controlled receptacles automatically regain power when occupant enters.

#### When Occupied:

Manual: Occupant uses wall dimmer to set desired light levels for all lights.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

50% of all receptacles automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

Lighting Energy Savings\*


45%

**Code Notes:** For break rooms with daylight, include a 0-10V dimming module per zone and a daylight sensor. Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

<sup>\*</sup> Go to lutron.com/references for more information

### Classroom | Retrofit

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-16R-DV-B	PowPak switching module	2	\$ 155.00
	LRF2-VKLB-P-WH	Radio Powr Savr wireless corner-mount vacancy sensor	1	\$ 105.00
	PJ2-2B-GWH-L01	Pico wireless 2-button control	2	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	2	\$ 9.50

# Visible System Components





Pico wireless control

Radio Powr Savr wireless corner-mount vacancy sensor

# **Control Strategies**



# **Control Functionality**

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually.

#### When Occupied:

Manual: Occupant uses wall switches to turn on and turn off general and white-board lighting.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.


Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

Lighting Energy Savings\*

<sup>\*</sup> Go to lutron.com/references for more information.

### **Classroom | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	4	\$ 180.00
	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	LRF2-DCRB-WH	Radio Powr Savr wireless daylight sensor	1	\$ 150.00
	LRF2-VKLB-P-WH	Radio Powr Savr wireless corner-mount vacancy sensor	1	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	2	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	2	\$ 9.50

#### Code Notes: For non-daylit classrooms, all general lighting can be connected to a single 0-10V dimming module. Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

# Visible System Components





Pico wireless control

**Occupant Enters:** 

When Occupied:

Control Functionality

Controlled receptacles automatically regain power when occupant enters.

Automatic: Overhead lights dim/brighten based on daylight availability. There are

Manual: Occupant uses wall dimmers to set desired light levels for both general

All lights automatically turn off 15 minutes

50% of all receptacles automatically turn off

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

15 minutes after all occupants exit.

two perimeter daylight zones.

and white-board lights.

after all occupants exit.

**Occupant Exits:** 

Lights do not automatically turn on when an

occupant enters the space; lights must be turned

on manually. Maximum light level is set to 80%.

Radio Powr Savr

# **Control Strategies**




Occupancy/Vacancy



**Daylight Harvesting** 





**High-end Trim/Tuning** 







wireless corner-mount vacancy sensor and daylight sensor





**Personal Dimming** 



**Plug Load Control** 

# Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information

#### Classroom | Recommended

ASHRAE 90.1-2013

# Line-voltage wiring Clear Connect RF Communication 1 integrated into each light fixture

Symbol	Model Number	Description	Qty	List Price Each
0 0	Integral to fixture <sup>1</sup>	Integral fixture control with sensor	12	\$ 78.00 <sup>2</sup>
	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	PJ2-4B-GWH-L31	Pico wireless 4-button scene control	1	\$ 45.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	2	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	3	\$ 9.50

1 Fixture control comes pre-installed in fixture. Look for the Clear Connect Wireless symbol for fixtures containing this module. Go to lutron.com/findafixture for a complete list of compatible fixtures and drivers.



2 Fixture adder for the control module may vary.

# Visible System Components





Pico wireless

scene control

4-button



Integral fixture control with sensor





#### **Control Functionality**

#### **Occupant Enters:**

Pico wireless control

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually. Maximum light level is set to 80%.

Controlled receptacles automatically regain power when occupant enters.

#### When Occupied:

Automatic: Overhead lights dim/brighten based on daylight availability. There are two perimeter daylight zones.

Manual: Occupant selects scenes or uses dimmers to set desired light levels for all lights. Entry scene controller has 3 user preferred presets and 1 all off button.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

50% of all receptacles automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# **Control Strategies**





Scene Control



**Daylight Harvesting** 



**Personal Dimming** 



**High-end Trim/Tuning** 



Plug Load Control

# Lighting Energy Savings\*




<sup>\*</sup> Go to lutron.com/references for more information

Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires digitally enabled ballasts and drivers by others.

### **Conference Room | Retrofit**

ASHRAE 90.1-2013





#### List Price Each Symbol Model Number Description Qty RMJS-16R-DV-B PowPak switching module \$ 155.00 Radio Powr Savr wireless corner-mount LRF2-VKLB-P-WH \$ 105.00 vacancy sensor PJ2-2B-GWH-L01 Pico wireless 2-button control \$ 27.00 1 PICO-WBX-ADAPT Pico wallbox adapter \$ 9.50 1

# Visible System Components






Pico wireless control

Radio Powr Savr wireless corner-mount vacancy sensor

# Control Strategies



# **Control Functionality**

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually.

#### When Occupied:

Manual: Occupant uses wall switch to turn all lights off.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

Lighting Energy Savings\*

40%

<sup>\*</sup> Go to lutron.com/references for more information.

#### **Conference Room | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	2	\$ 180.00
2	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	LRF2-DCRB-WH	Radio Powr Savr wireless daylight sensor	1	\$ 150.00
	LRF2-VKLB-P-WH	Radio Powr Savr wireless corner-mount vacancy sensor	1	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	2	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	2	\$ 9.50

#### Code Notes: For non-daylit conference rooms, all general lighting can be connected to a single 0-10V dimming module. Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

# Visible System Components








Radio Powr Savr wireless corner-mount vacancy sensor and daylight sensor

# **Control Strategies**



Occupancy/Vacancy





**Personal Dimming** 







**Occupant Enters:** 

When Occupied:

**Occupant Exits:** 

after all occupants exit.

**Control Functionality** 

Controlled receptacles automatically regain power when occupant enters.

Automatic: Overhead lights dim/brighten based on daylight availability. There are

Manual: Occupant uses wall dimmer to set desired light levels for all lights.

All lights automatically turn off 15 minutes

50% of all receptacles automatically turn off

Add a Vive wireless hub to enable simple setup

and rezoning, system monitoring, timeclock functionality, and advanced integration.

15 minutes after all occupants exit.

two perimeter daylight zones.

Lights do not automatically turn on when an

occupant enters the space; lights must be turned

on manually. Maximum light level is set to 80%.





**Daylight Harvesting** 



**High-end Trim/Tuning** 



**Plug Load Control** 

# Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.

#### **Conference Room | Recommended**

ASHRAE 90.1-2013

# DZ 1 DZ 1 DZ 2 DZ 2 DZ 2

Line-voltage

Clear Connect

DZ 1 & DZ 2 = **Daylight Zones** 



1 required for each light fixture



1 required for each light fixture

#### List Price Each Symbol Model Number Description Qty EcoSystem-enabled Hi-Lume Soft-on, Multiple 10 Consult your local rep Fade-to-Black series ballasts/drivers FCJS-ECO Wireless fixture control with EcoSystem 10 \$ 91.00 RMJS-20R-DV-B 20A PowPak relay module \$ 170.00 1 LRF2-DCRB-WH Radio Powr Savr wireless daylight sensor \$ 150.00 1 Radio Powr Savr wireless corner-mount LRF2-VKLB-P-WH \$ 105.00 vacancy sensor 2 PJ2-4B-GWH-L31 \$ 45.00 Pico wireless 4-button scene control PICO-WBX-ADAPT 2 \$ 9.50 Pico wallbox adapter

#### Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. Go to lutron.com/ballasttool or lutron.com/findafixture to identify the correct ballast or LED fixture for your project.





**Occupant Enters:** 

When Occupied:

1 all off button.

**Occupant Exits:** 

after all occupants exit.

Control Functionality

Controlled receptacles automatically

regain power when occupant enters.

Automatic: Overhead lights dim/brighten

Manual: Occupant selects scenes to set desired light levels for all lights. Entry scene

controller has 3 user preferred presets and

All lights automatically turn off 15 minutes

50% of all receptacles automatically turn off

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

15 minutes after all occupants exit.

based on daylight availability. There are

two perimeter daylight zones.

Lights do not automatically turn on when an


occupant enters the space; lights must be turned

on manually. Maximum light level is set to 80%.




Radio Powr Savr wireless corner-mount vacancy sensor and daylight sensor

## **Control Strategies**



Occupancy/Vacancy



Full On Dim

**Daylight Harvesting** 





**High-end Trim/Tuning** 



# Visible System Components



Pico wireless 4-button







**Personal Dimming** 



Plug Load Control

# Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information

Model Number

RMJS-16R-DV-B

LRF2-OHLB-P-WH

PJ2-2B-GWH-L01

PICO-WBX-ADAPT

### **Egress Corridor | Retrofit**

ASHRAE 90.1-2013

# Visible System Components









Radio Powr Savr wireless hallway occupancy sensor



# **Control Functionality**

#### **Occupant Enters:**

All non-emergency lights automatically turn on to maximum light level.

#### When Occupied:

Manual: Occupant uses wall switch to turn all non-emergency lights off.

#### **Occupant Exits:**

All non-emergency lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# **Control Strategies**



Lighting Energy Savings\*

To emergency power

Description

PowPak switching module

occupancy sensor

Pico wallbox adapter

Radio Powr Savr wireless hallway

Pico wireless 2-button control

Clear Connect RF Communication

Qty

2

2

List Price Each

\$ 155.00

\$ 105.00

\$ 27.00

\$ 9.50

Symbol

<sup>\*</sup> Go to lutron.com/references for more information.

Model Number

RMJS-8T-DV-B

LRF2-OHLB-P-WH

PJ2-3BRL-GWH-L01

PICO-WBX-ADAPT

#### **Egress Corridor | New Construction**

ASHRAE 90.1-2013

# Visible System Components







Radio Powr Savr wireless hallway occupancy sensor





Pico wireless control

Control Functionality

#### **Occupant Enters:**

All lights automatically turn on to maximum light level. Maximum light level is set to 80%.

#### When Occupied:

Manual: Occupant uses wall dimmer to set desired light levels for all lights. Manual control cannot fully shut off the lights. Minimum light level is set to 10%.


#### **Occupant Exits:**

All lights automatically go to minimum light level15 minutes after all occupants exit.

#### **Emergency Mode:**

Lighting connected to emergency power turns on to full output.

# **Control Strategies**





**High-end Trim/Tuning** 

#### Code Notes: Verify that the egress fixtures go to full output upon loss of control signal. For projects that require UL 924 compliance, provide an automatic load control relay (ALCR) per load controller connected to emergency fixtures. Add a daylight sensor for corridors with daylight zones. Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

To emergency power

Description

Pico wireless 3-button with raise/lower control

PowPak dimming module with 0-10V

Radio Powr Savr wireless hallway

occupancy sensor

Pico wallbox adapter

Clear Connect RF Communication

Qty

2

2

List Price Each

\$ 180.00

\$ 105.00

\$ 27.00

\$ 9.50

Code Notes: For non-egress corridors, set the minimum light level to full off.


\* Go to lutron.com/references for more information.

Lighting Energy Savings\*

Symbol

# **Open Office | Retrofit**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	1	\$ 180.00
	LRF2-OCR2B-P-WH	Radio Powr Savr wireless ceiling-mount occupancy sensor	4	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# Visible System Components







Pico wireless control

Radio Powr Savr wireless ceiling-mount occupancy sensor

# Control Strategies



Occupancy/Vacancy



**High-end Trim/Tuning** 

# **Control Functionality**

#### **Occupant Enters:**

All lights automatically turn on to 50% light level. Maximum light level is set to 80%.

#### When Occupied:

Manual: Occupant uses wall dimmer to set desired light levels for all lights.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.


Lighting Energy Savings\*

45%

<sup>\*</sup> Go to lutron.com/references for more information.

### **Open Office | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	3	\$ 180.00
2	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	LRF2-DCRB-WH	Radio Powr Savr wireless daylight sensor	1	\$ 150.00
	LRF2-OCR2B-P-WH	Radio Powr Savr wireless ceiling-mount occupancy sensor	4	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# **Code Notes:** For non-daylit open offices, all general lighting can be connected to a single 0-10V dimming module. Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

# Visible System Components







Radio Powr Savr wireless ceiling-mount occupancy sensor and daylight sensor

# TO TO





## **Control Functionality**

#### **Occupant Enters:**

All lights automatically turn on to 50% light level. Occupant turns on lights to maximum level manually. Maximum light level is set to 80%.

Controlled receptacles automatically regain power when occupant enters.

#### When Occupied:

Automatic: Overhead lights dim/brighten based on daylight availability. There are two perimeter daylight zones.

Manual: Occupant uses wall dimmers to set desired light levels for all lights.


#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.


50% of all receptacles automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

#### **Control Strategies**



Occupancy/Vacancy



**Daylight Harvesting** 



**High-end Trim/Tuning** 



Plug Load Control


# Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information

#### **Open Office | Recommended**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
0 0	Integral to fixture <sup>1</sup>	Integral fixture control with sensor	16	\$ 78.002
2	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

1 Fixture control comes pre-installed in fixture. Look for the Clear Connect Wireless symbol for fixtures containing this module. Go to lutron.com/findafixture for a complete list of compatible fixtures and drivers.



2 Fixture adder for the control module may vary.

# Visible System Components







Integral fixture control with sensor





## **Control Functionality**

#### **Occupant Enters:**

Each individual light automatically turns on to 50% light level as occupant approaches fixture proximity. Maximum light level is set to 80%.

Controlled receptacles automatically regain power when occupant enters.

#### When Occupied:

Automatic: Each individual overhead light dims/brightens based on local daylight availability.

Manual: Occupant uses wall dimmer to set desired light levels for all lights.


#### **Occupant Exits:**

Each individual light automatically turns off 15 minutes after all occupants exit fixture proximity.

50% of all receptacles automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# **Control Strategies**




Occupancy/Vacancy



**Daylight Harvesting** 



**High-end Trim/Tuning** 



Plug Load Control

# Lighting Energy Savings\*




<sup>\*</sup> Go to lutron.com/references for more information

Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires digitally enabled ballasts and drivers by others.

### **Private Office | Retrofit**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
N. Control of the con	RMJS-16R-DV-B	PowPak switching module	1	\$ 155.00
	LRF2-VCR2B-P-WH	Radio Powr Savr wireless ceiling-mount vacancy sensor	1	\$ 105.00
	PJ2-2B-GWH-L01	Pico wireless 2-button control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# Visible System Components





Pico wireless control

Radio Powr Savr wireless ceiling-mount vacancy sensor

# Control Functionality

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually.

#### When Occupied:

Manual: Occupant uses wall switch to turn all lights off.

#### **Occupant Exits:**


All lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# \*



# Control Strategies



# Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.

43

#### **Private Office | New Construction**

ASHRAE 90.1-2013

# Line-voltage wiring Low-voltage wiring Clear Connect RF Communication DZ 1 & DZ 2 = Daylight Zones 1 required for each fixture control

Symbol	Model Number	Description	Qty	List Price Each
	FCJS-010	Wireless fixture control with 0-10V	2	\$ 91.00
O. C.	RMJS-20R-DV-B	20A PowPak relay module	1	\$ 170.00
•••	FC-SENSOR	PowPak fixture sensor	2	\$ 40.50
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

**Code Notes:** FCJS models are capable of controlling up to 3 ballasts or drivers. Review the "Vive PowPak Fixture Controls" submittal document for more design details.

Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

# Visible System Components





Pico wireless control

PowPak fixture sensor

# Control Functionality

#### **Occupant Enters:**

Lights do not automatically turn on when an occupant enters the space; lights must be turned on manually. Maximum light level is set to 80%.

Controlled receptacles automatically regain power when occupant enters.

#### When Occupied:

Automatic: Overhead lights dim/brighten based on daylight availability. There are two perimeter daylight zones.

Manual: Occupant uses wall dimmer to set desired light levels for all lights.


#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.


50% of all receptacles automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# Control Strategies



Occupancy/Vacancy



**Daylight Harvesting** 



**Personal Dimming** 



**High-end Trim/Tuning** 



Plug Load Control

# Lighting Energy Savings\*




<sup>\*</sup> Go to lutron.com/references for more information

# Multi-Stall Restroom | Retrofit

ASHRAE 90.1-2013

# Line-voltage wiring Clear Connect



Symbol	Model Number	Description	Qty	List Price Each
2 B	RMJS-16R-DV-B	PowPak switching module	1	\$ 155.00
	LRF2-OCR2B-P-WH	Radio Powr Savr wireless ceiling-mount occupancy sensor	2	\$ 105.00
	PJ2-2B-GWH-L01	Pico wireless 2-button control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# Visible System Components





Pico wireless control

Radio Powr Savr wireless ceiling-mount occupancy sensor

# **Control Functionality**

#### **Occupant Enters:**

All lights automatically turn on to maximum light level.

#### When Occupied:

Manual: Occupant uses wall switch to turn all lights off.


#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.



# **Control Strategies**




Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.

# **Multi-Stall Restroom | New Construction**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	RMJS-8T-DV-B	PowPak dimming module with 0-10V	1	\$ 180.00
	LRF2-OCR2B-P-WH	Radio Powr Savr wireless ceiling-mount occupancy sensor	2	\$ 105.00
	PJ2-3BRL-GWH-L01	Pico wireless 3-button with raise/lower control	1	\$ 27.00
	PICO-WBX-ADAPT	Pico wallbox adapter	1	\$ 9.50

# Visible System Components





Pico wireless control

Radio Powr Savr wireless ceiling-mount occupancy sensor

# **Control Functionality**

#### **Occupant Enters:**

All lights automatically turn on to maximum light level. Maximum light level is set to 80%.

#### When Occupied:


Manual: Occupant uses wall dimmer to set desired light levels for all lights.

#### **Occupant Exits:**

All lights automatically turn off 15 minutes after all occupants exit.

Add a Vive wireless hub to enable simple setup and rezoning, system monitoring, timeclock functionality, and advanced integration.

# Control Strategies







High-end Trim/Tuning

Lighting Energy Savings\*




<sup>\*</sup> Go to lutron.com/references for more information.

**Code Notes:** Add a daylight sensor for restrooms with daylight zones.

Want to add a Vive wireless hub for more features? Go to lutron.com/vive for complete compatibility and design details. This solution requires 0-10V enabled ballasts and drivers by others.

### **Egress Stairwell | Retrofit**

ASHRAE 90.1-2013



Symbol	Model Number	Description	Qty	List Price Each
	FXSWLX4H	Lutron 4 ft. stairwell LED fixture	2 (per floor)	\$ 720.00
	LRF2-OKLB-P-WH	Radio Powr Savr wireless corner-mount occupancy sensor	1 (per floor)	\$ 105.00

# Visible System Components







Radio Powr Savr wireless corner-mount occupancy sensor

# **Control Functionality**

#### **Occupant Enters:**

All lights automatically turn on to maximum light level. Maximum light level is set to 80%.


#### **Occupant Exits:**

All lights dim to minimum light level 15 minutes after all occupants exit. Minimum light level is set to 10%.

#### **Emergency Mode:**

Lighting connected to emergency power turns on to full output.

### **Control Strategies**



Occupancy/Vacancy



High-end Trim/Tuning

Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.

Code Notes: Verify that the egress fixtures go to full output upon loss of control signal. For projects that require UL 924 compliance, provide an automatic load control relay (ALCR) per load controller connected to emergency fixtures. Add a daylight sensor for stairwells with daylight zones. The Lutron Stairwell Fixture (FXSWLX44) is not currently compatible with the Vive wireless hub. A new model number is coming soon that will include Vive compatibility. Go to lutron.com/vive for the latest compatibility details.

**Code Notes:** For non-egress stairwells, see the new construction solution and set the minimum light level to full off.

### **Egress Stairwell | New Construction**

ASHRAE 90.1-2013

# Line-voltage wiring Clear Connect RF Communication To emergency power 1 integrated into each light fixture A floor cross-section is shown. One fixture per landing is suggested.

Symbol	Model Number	Description	Qty	List Price Each
0	Integral to fixture <sup>1</sup>	Integral fixture control	2 (per floor)	\$ 67.002
	LRF2-OKLB-P-WH	Radio Powr Savr wireless corner-mount occupancy sensor	1 (per floor)	\$ 105.00

1 Fixture control comes pre-installed in fixture. Look for the Clear Connect Wireless symbol for fixtures containing this module. Go to lutron.com/findafixture for a complete list of compatible fixtures and drivers.



# Visible System Components





Radio Powr Savr wireless corner-mount occupancy sensor

Integral fixture control

# Control Functionality Control S

#### **Occupant Enters:**

All lights automatically turn on to maximum light level. Maximum light level is set to 80%.


#### **Occupant Exits:**

All lights dim to minimum light level 15 minutes after all occupants exit. Minimum light level is set to 10%.

#### **Emergency Mode:**

Lighting connected to emergency power turns on to full output.

# **Control Strategies**





**High-end Trim/Tuning** 

Lighting Energy Savings\*



<sup>\*</sup> Go to lutron.com/references for more information.

<sup>2</sup> Fixture adder for the control module may vary.

**Code Notes:** Verify that the egress fixtures go to full output upon loss of control signal. For projects that require UL 924 compliance, provide an automatic load control relay (ALCR) per load controller connected to emergency fixtures. Add a daylight sensor for stairwells with daylight zones. This solution requires digitally enabled ballasts and drivers by others.

Clear Connect, EcoSystem, Hi-Lume, Lutron, Maestro, Pico, PowPak, and Quantum are trademarks of Lutron Electronics Co., Inc., registered in the U.S. and other countries. Energi Savr Node, Radio Powr Savr, and Vive are trademarks of Lutron Electronics Co., Inc.

#### **Contact Lutron**

lutron.com Lutron Electronics Co., Inc., 7200 Suter Road, Coopersburg, PA 18036-1299

#### **Customer Assistance**

Online: lutron.com/help Email: support@lutron.com

Phone: 1.844.LUTRON1 (588.7661) — includes 24/7 technical support

 $\ \odot$  07/2022 Lutron Electronics Co., Inc.  $\ |$  P/N 367-2623 REV F

















